

DIKGATLONG LOCAL MUNICIPALITY



ADVERTISEMENT FORMAL WRITTEN PRICE QUOTATION FOR SEVEN DAYS NOTICE

BID NO: RFQ14/2025/26

Dikgatlong Municipality hereby invites suitably prospective service providers to quote for **relocating of mv supply, upgrading of transformer and installing ariel bundle conductor** clearly endorsed "RFQ14/2025/26 **RELOCATING OF MV SUPPLY, UPGRADING OF TRANSFORMER AND INSTALLING ARIEL BUNDLE CONDUCTOR**" on the envelope must be submitted **on the tender box** situated at the reception area of Dikgatlong Local Municipality, 33 Campbell Street, Barkly West, 8375.

Bids **must** reach the municipality before **10h30 on Friday the 12th of December 2025**.

BACKGROUND AND SPECIFICATIONS/ SCOPE OF WORK PURPOSE

PURPOSE

A site inspection was conducted at the location shown in the attached pictures. The current 11kV overhead power line runs through the middle of a public sitting area with an estimated clearance of approximately 4.5m from the ground. The area is frequently used by the community on a daily basis.

During a recent incident, the area experienced severe flooding where water levels rose to over 1 metre above ground level. This increases the danger significantly, as the presence of standing water beneath high-voltage infrastructure elevates the risk of electrical shocks, flashovers, and touch potential hazards. In such conditions, the risk extends beyond accidental contact, and becomes a broader public safety concern. Given the current placement of the MV line, if an electrical incident were to occur, the municipality may be held accountable as the infrastructure does not meet safe public clearance guidelines. This exposes the municipality to potential legal, operational, and reputational consequences.

The existing 200kVA transformer is currently operating on maximum capacity and has shown signs of strain during peak electricity demand. Upgrading the transformer to a 315kVA unit will improve system reliability, reduce overloading, and support future load growth. Once the new power line and transformer are in service, the existing MV line section must be dismantled to prevent redundant unsafe infrastructure.



4. Scope of Work

Items	Descriptions	Quantity
1.	Digging of pole holes, 1,8m deep	13
2.	H-pole structure construction, which include planting 11m pole	2
3.	Digging stay hole MV 1.8m	2
4.	Planting and compaction of 9m poles	6
5.	Supply and installation of stays and its accessories	2
6.	Construction of a transformer platform, a platform will consist of 5 poles structure. Digging 5x1.8m deep holes, 5x planting and compaction of 11m holes.	1
7.	Stay plate to install on pole hole, hence area is near the river	10
8.	Supply and installation of 2m channel iron	4
9.	Installation of 315KVA transformer	1
10.	Supply and installation of transformer earthing system	1
11.	Supply and installation of surge arrestors for 315kVA transformer	3
12.	Installation of crossarm 2.5m	1
13.	Supply and installation of 3.5m crossarm on H-pole structure	1
14..	Installation of Ariel Bundle Conductor	500m
15.	Dismantling of old MV power line	1
16.	Dismantling old LV power line	1
17.	Disconnecting of current transformer and dismantling platform	1
18.	Transporting of all dismantled material/units/conductor etc to	1

	technical stores	
19.	Crane Hire	1

1. Late, emailed, faxed, incomplete quotes will not be considered.
2. All quotes will be adjudicated and awarded in terms of the Dikgatlong Local Municipality Procurement and Supply Chain Management Policy, the Preferential Procurement Policy Framework Act, Act No. 5 of 2000 and the regulations promulgated under this Act. This bid is

subject to the General Conditions of Contract and, if applicable, any other Special Condition of Contract.

3. Quotes must be valid for a period of 30 days

4. Suppliers must submit their quotes with the following documentation and or information:

4.1 A valid original Tax Clearance certificate or a valid tax pin.

4.2 **A certificate certifying that the bidder has no undisputed commitments for Municipal services towards a municipality or service provider i.r.o. payments which are overdue more than 90 days; if the bidder is the lessee a valid lease agreement together with the municipal account of the landlord; or a letter from tribal authority if the service provider operates in rural area.**

4.3 MBD 4, 6.1, 8 and 9 must be fully completed and submitted together with a quotation.

4.4 Bidders must be registered on the Central Supplier Data Base.

4.5 The tender will be evaluated in terms of the 80/20 preference points system of which 80 points will be for price and 20 points for specific goals (Locality and HDI) as illustrated below

SPECIFIC GOALS		
Historical disadvantaged Individuals (10 max points)	Locality (10 max points)	
Number of Points for HDI	Locality	Number of Points for Locality
10 points will be awarded to the service provider with more than 50% ownership of the business by HDI.	Within the boundaries of Dikgatlong Local Municipality	10
	Within the boundaries of Frances Baard District Municipality	8
	Within the boundaries of Northern Cape	6
	Within the boundaries of South Africa	4

5. Address and the vat number (4450111283) of the municipality must appear on the quote.
6. The payment will only be done once the service provider has completed the project, therefore not partial payments will be done.
7. Minimum CIDB required for this job is **1EP**
8. Failure to meet the above requirements or submission of documents will lead to disqualification of the bid.

The Municipality does not bind itself to accept the lowest or any bid and reserves the right to accept the whole or only part of a bid if (a) the bid amounts received are too high; (b) the bids do not comply with the specific bid goals; or (c) objective criteria exist which justify or necessitate the non-acceptance of any bids.

Enquiries must be directed to: SCM Office at Tel no: (053) 531 6500 or email m.gawuzela@dikgatlong.gov.za

Ms. B Tsinyane
Municipal Manager
Notice date: 04/12/2025